

ITEM	QTY	DESCRIPTION			
1	1 EA	CLOSE EXISTING CORP STOP			
2	1 EA	INSTALL THREADED BRONZE CAP ON CORP STOP, FEMALE OR SOLDERED CAP			
3	1 EA	CLOSE LOCKWING ANGLE VALVE			
4	1 EA	REMOVE METER AND RETURN TO SBMWD METER SHOP			
1) (2) (3) (4) (5) (6) (7)	1 EA	CLOSE BALL VALVE			
<u>(6)</u>	1 EA	PRIVATE SERVICE LINE TO REMAIN IN-PLACE			
(7)	1 EA	REMOVE METER BOX LID (METERS LOCATED IN CONCRETE) OR REMOVE ENTIRE METER BOX (METERS LOCATED OUTSIDE CONCRETE)			
8	1 EA	BACKFILL METER BOX WITH SELECT BACKFILL AND COMPACT TO = 85% MAX DENSITY			
9	1 EA	INSTALL CONCRETE SIDEWALK PER CITY OF SAN BERNARDINO STANDARDS TO NEAREST CONSTRUCTION JOINT			
10	1 EA	BACKFILL AND PAVEMENT REPLACEMENT PER SBMWD STD. DWG. W5.1			

REVISION DATE: 1/24/2011

D.D.M.	JAN. 11	SAN BERNARDIN	DRAWING		
M.J.N.	FEB. 10				NUMBER
C.L.R.	NOV. 05	SERVICE A	SBMWD		
M.J.N.	FEB. 04	SERVICE A			
REVISION	DATE	ADDDOVED	DATE	07/04/2040	W1.16
scale: NONE		APPROVED WARR	N HUANG, P.E. RCE 49208	07/04/2019	