

- 1. REFER TO THE SBMWD DESIGN PLANS AND TECHNICAL SPECIFICATIONS WHERE APPLICABLE.
- 2. FOR USE AS TRENCH BACKFILL STABILIZATION.
- 3. THE DETAILS SHOWN REPRESENT THE MINIMUM REQUIREMENTS. CONTRACTOR SHALL PROVIDE A SUBMITTAL TO SBMWD FOR REVIEW AND APPROVAL PRIOR TO INSTALLATION.
- 4. WALLS SHALL BE REINFORCED CONCRETE OR 8" X 8" X 16" CONCRETE BLOCK, REINFORCED AND ALL CORES FILLED WITH GROUT PER THE SPECIFICATIONS.
- 5. SBMWD STANDARD DRAWING W6.15 SHALL BE CONSIDERED AND INSTALLED ON A CASE BY CASE BASIS AS DETERMINED BY SBMWD.
- 6. REFER TO SBMWD STANDARD DRAWING W5.1 FOR TRENCH WIDTH AND DEPTH REQUIREMENTS.

**REVISION DATE: 3/29/2016** 

		SAN BERNARDINO MUNICIPAL WATER DEPARTMENT		DRAWING NUMBER
		CUT-OFF WALL		
F.D.L.	MAR. '16	FOR GRADES	\ \\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\	
REVISION	DATE	APPROVED	DATE 07/04/2019	W6.15
scale: NONE		WARREN HUANG, P.E. RCE	49208	